

Phius Con 2021 Phius QA Things You Need To Know as a Phius Rater & Verifier

• Isaac Elnacave – Phius Certification Staff

- James Ortega, RA Phius Certification Manager
- Anthony Lisanti, CEM CPHC Phius QA/QC Manager



- Agenda
 - PHIUS Updates
 - Phius 2021
 - Air Tightness Testing
 - Energy Star & IAP Updates
 - Summary
 - Questions, comments, feedback?







• QA/QC Process

- Thank you to PHIUS Staff (Lisa, James & Isaac)- it is a Team effort!
- Isaac continues to expand QA Review process
- QA/QC Process:
 - Certification Process:
 - Pre-screening PHIUS submissions for document completeness
 - On going updates with Certification Team
 - QA Workbooks for SF & MF & Non-Res




- For 2021 there are 3 options:
 - Phius 2021 CORE (formerly known as PHIUS+ Core) All Bldgs
 - Phius 2021 CORE Prescriptive (Single Family Only)
 - Phius 2021 ZERO (formerly known as PHIUS+ Source Zero) All Bldgs





- Phius 2021 CORE Prescriptive Path
 - Single Family and Townhomes only
 - Not qualified for Phius ZERO
 - No WUFI Modeling required
 - CPHC not required (recommended)
 - Project Specific Prescriptive Checklist need to be met







IECC 2009	IECC 2012	ENERGY STAR v3	ENERGY STAR v3.1	ZERO ZERH	PHIUS PHIUS+	<u>+C</u> PHIUS+ SourceZero
HERS 85-90	HERS 70-80	HERS 65-75	HERS 55-65	HERS 48-55	HERS 35-45	HERS < 0
IECC 2009 Enclosure	IECC 2012 Enclosure	IECC 2009 Enclosure	IECC 2012 Enclosure	IECC 2012/15 Encl./ES Win.	Ultra-Efficient Enclosure	Ultra-Efficient Enclosure
		Independent Verification	Independent Verification	Independent Verification	Independent Verification	Independent Verification
		Water Management	Water Management	Water Management	Water Management	Water Management
		HVAC QI w/WHV	HVAC QI w/WHV	HVAC QI w/WHV	Micro-load HVAC QI	Micro-load HVAC QI
				Ducts in Condit. Space	Ducts in Condit. Space	Ducts in Condit. Space
				EPA Indoor airPLUS	EPA Indoor airPLUS	EPA Indoor airPLUS
				Eff. Comps. & H2O Distrib	Eff. Comps. & H ₂ O Distrib	Eff. Comps. & H ₂ O Distrib
				SOLAR READY Depends on climate	SOLAR READY ALWAYS	SOLAR READY ALWAYS
					Balanced Ventilation HRV/ERV	Balanced Ventilation HRV/ERV
						Source Zero Renew- able Energy System



- January 1, 2022: All new projects must follow Phius 2021
 - EPA Energy Star MFNC Required beginning July 1, 2021 (includes PHIUS 2018 projects)
 - All MF Projects must be certified under EPA MFNC
 - All SF Projects and/or Townhomes Certified under EPA SF Homes
 - All Dwellings Certified/or follow EPA Indoor airPLUS
 - DOE ZERH



- Phius 2021 Quality Assurance
 - SF QA Workbook for Prescriptive and ZERO
 - EPA Energy Star Single-Family New Homes
 - EPA Indoor airPLUS V1 Rev 4.0
 - New version out for comment 2021/2022
 - DOE ZERH Rev 7 May 2019
 - MF QA Workbook- new version based on EPA MFNC v1/1.1 (Rev 02)
 - Non-Residential QA Workbook



- Phius 2021 Quality Assurance
 - SF Prescriptive or Source Zero
 - MF QA Workbook- new version with EPA MFNC
 - EPA Energy Star Multifamily New Construction Program July 1, 2021
 - EPA Indoor airPLUS V1 Rev 4.0
 - » Certification required for all Bldg 5 stories & below
 - » Checklist applied to all Bldgs greater than 5 stories
 - DOE ZERH Rev 7
 - DWH Temp Rise/Performance applied to all dwelling units
 - PV Ready Checklist applied to building
 - Non-Residential QA Workbook



- Energy Star & IAP Updates
 - ENERGY STAR PROGRAM
 - HERS Raters Must complete Mandatory Energy Star MF Training through a RESNET Training Provider



- Phius 2021
 - Air-Tightness:

Perfor	mance		Prescriptive			
Building Type	50 Pa	75 Pa	Building Type	50 Pa	75 Pa	
≥5 Stories &	q≤ 0.080	q≤ 0.110	Single-family			
Non-combustible*	CFM_{50}/ft^2	CFM ₇₅ /ft ²	detached,	q≤ 0.040	q≤ 0.053	
All other buildings	q≤ 0.060	q≤ 0.080	attached and	CFM ₅₀ /ft ²	CFM ₇₅ /ft ²	
All other buildings	CFM_{50}/ft^2	CFM ₇₅ /ft ²	townhomes			

*Non-combustible in this sense is construction that is not subject to mold and rot. This would mean no wood-based framing members or sheet goods, and no wood-based or paper-based insulation.

> Phius 2021 CORE Prescriptive: Requires Preliminary Blower Door Test!

- Please indicate Building Configuration On the Report
 - taped/untaped
- Dwelling Unit Compartmentalization = 0.30 CFM/SF



• Air Tightness Testing – ANSI/RESNET/ICC STANDARD 380-2019, November 21, 2018



Standard for Testing Airtightness of Building, Dwelling Unit, and Sleeping Unit Enclosures; Airtightness of Heating and Cooling Air Distribution Systems; and Airflow of Mechanical Ventilation Systems



November 21, 2018

Residential Energy Services Network, Inc. P.O. Box 4561 Oceanside, CA 92052-4561 http://resnet.us/

International Code Council 500 New Jersey Avenue, NW, 6th Floor Washington, D.C. 20001 www.iccsafe.org

©Residential Energy Services Network, 2018. All rights reserved.



- Air Tightness Testing
 - Pressurization
 - Depressurization
 - Avg. of both multi-point tests
 - Test reports to be provided for both
 - Test Reports shall document a passing score based on PHIUS Air tightness limits
 - Correlation Coefficient no worse than 0.95
 - Projected Accuracy of +/- 10%
 - please check before submitting data for review
 - Envelope Areas to be consistent



- Air Flow Measurement
 - Preliminary & Final Air Tightness Test reports provided
 - TAB & Air flow verification reports provided
 - Indicate Vent. Speed Setting (Low, Med, High) for Verification
 - Room Pressure Differential measured at Design Vent. Rate
 - Power Measurements- post balancing with clean filters
 - PHIUS + QA Workbook (SF or MF)



Summary

- Mandatory program prerequisites are not being completely met or being questioned
- PHIUS is left with difficult choice:
 - Overlook non-compliant items; undermine our agreement with DOE
 - Fail otherwise compliant homes for "relatively small" issues
- Complicates and extends QA review time
- It's project team's responsibility to deliver compliant project
 - You are responsible for verifying compliance
 - You also should be an asset in identifying potential non-compliance as early as possible
 - Issues with Underpinning Programs are best directed to those Programs and/or your QA Provider



qa@phius.org

Thank you for attending!