

Engaging PHIUS Verification in Early Design

From a PHIUS Verifiers Perspective

Chris Straile
Senior Manager
Sustainable Comfort, Inc.

Greg Downing
Senior Project Manager
Sustainable Comfort, Inc.

Learning Objectives

Learning Objective 1: Understand the additional program requirements for PHIUS Certification

Learning Objective 2: Review how checklist programs and feedback can be incorporated into an iterative design process

Learning Objective 3: Review the Energy Star Multifamily milestones and additional modeling criteria

Learning Objective 4: Identify the major items sometimes overlooked in checklist-based energy programs



PHIUS+ Certification Process



Schematic Design: Initial Layout and Systems



Pre-Certification: Approved Modeling and CD's



Construction Inspections: Insulation & Air Sealing Checks



Final Testing: Air Tightness & Commissioning



Certification: Final Certifications

High-Performance
Home Staircase




PHIUS+ Certification Process

High-Performance
Home Staircase



Schematic Design: Initial Layout and Systems



Pre-Certification: Approved Modeling and CD's



Construction Inspections: Insulation & Air Sealing Checks



Final Testing: Air Tightness & Commissioning



Certification: Final Certifications





West Side Homes, Buffalo, NY


Owner: Buffalo Neighborhood Stabilization Company, Inc.
Design Team Lead: Sustainable Comfort, Inc.

Project Description


The Buffalo Neighborhood Stabilization Company Inc (BNSC), the housing development arm of PUSH Buffalo, proposes to develop 15 units of housing on Buffalo's West Side that is targeting certification with Passive House Institute US (PHIUS), and pursuing NYSERDA, 2020 Enterprise Green Communities, and WELL Building Certification. By coordinating housing and sustainability work, West Side Homes addresses both human and ecosystem health, creates a resilient project that addresses future heat, precipitation, and drought events, and uses renewable energy sources to avoid increased greenhouse gas emissions.

Project Information

Location	Buffalo, NY
Climate Zones	5A
Average HERS Index	<50 pre PV, <10 post PV
Square Footage	18,131 sf
No. of Units	15 Multifamily Units
Year Built	Anticipate 2021 Start



Energy Modeling Results [WUFI Passive]



Technical Details

Walls	Wood panelized construction, 2X6 cavity with R-20 dense pack cellulose. Utilizing 2.5" zip panels creating R-12.6 of continuous insulation totaling R-33 exterior wall, finished with LP Smartside.
Windows	Alpen Tyrol Triple Pane Casement Windows
Air Barrier	The exterior ZIP sheathing will create an enhanced air, water, moisture and thermal barrier.
Roof	R-30+ continuous insulation
Slab	Continuous EPS perimeter and under-slab insulation
Heating/Cooling	Ground Source Heat Pump
Ventilation	The ERV ventilation system has monitoring capabilities allowing tenants to track some aspects of indoor air quality.
Hot Water	Geothermal electric hot water with desuperheaters
Solar Electric	Roof-mounted Solar Photovoltaic systems owned by BNSC will produce an estimated 30,755 kWh/yr
Materials	Low carbon materials such as insulation and foam were considered during material selection process.

Targeted Certifications

- PHIUS+ 2018 & Source Zero,
- NYSERDA Low Rise New Construction Program Tier III
- 2020 Enterprise Green Communities
- WELL Building Certification

Partners



tary and Confidential






Design Review




PHIUS+					
66	PHIUS Certification		Mechanical	Exhaust going into return side of common area AHU	Clarify
67	PHIUS Verification		Mechanical	1.3a: All ventilation air inlets located at least 10' ("stretched-string distance") from known contamination sources 1.3b: All ventilation air inlets located minimum 5' from ventilation exhaust outlet, recommended 10' 1.6: Outside air passes through a minimum MERV 8 filter prior to distribution, is changed at final and home is ventilated prior to occupancy 1.7: Outside air filter is located to facilitate regular service by the occupant and/or building superintendent 1.8: Air-sealed, class 1 vapor retarder shall be installed over all air-permeable insulation (such as fiberglass duct wrap) on ventilation ducts connected to outside 1.10: Dedicated Fresh Air supply to all bedrooms Fresh air (OA) supply to bedrooms is required in all dwelling units: • In the case of ventilation ductwork integrated with heating/cooling ducts, the heating/cooling air handler fan must be designed to run continuously by default. 1.14: If kitchen exhaust connected to ERV/HRV, register is min. 6' from cooktop, MERV 3 or washable mesh filter for trapping grease, and recirc hood over range	
Ceiling/Attic					
68	PHIUS detailing	A-402 RI	Architect	Add notes to spray foam flash layer to air seal above ceiling plan or similar	Primary air barrier
69	WUFI Energy Model	A-402 RI	Architect	Change batts to cellulose and correct R-value	Need higher R-value for PHIUS modeling
70	PHIUS detailing	A-402 RI	Architect	Does poly need to be spec'd at ceiling plane?	Building science question
Walls					
71	PHIUS detailing	A-402 RI & West	Architect	Suggest Prosoco seams of ZIP rather than tape, flash windows with Zip Liquid Flash or Prosoco – At exterior layer	
72	PHIUS detailing	A-402 RI	Architect	Could potentially downgrade ZIP to osb at layer	
73	WUFI Energy Model	A-402 RI	Architect	Model has R-23 batts in 2x6 cavity	Increase Rhode Island wall cavity insulation value to R-23
74	PHIUS detailing	A-402 RI	Architect	Suggest Thermal buck at windows for connections. https://thermalbuck.com/	
75	PHIUS detailing	A-404 RI	Architect	Suggest mid-mounting windows for better psi value	To avoid any linear thermal bridging we've modeled windows as mid-mounted. Please consider a mid-mounted window.
Wall to foundation connection					
76	PHIUS detailing	A-402 RI	Architect	Stop ZIP-R "above grade, connect back to foundation with drip edge and trim to connect to concrete which will become air barrier	
77	PHIUS detailing	A-402 RI	Architect	Add EPS over top air barrier to connect to insulation extending below slab. Then cover EPS exposed above grade.	
78	PHIUS detailing	A-402 RI	Architect	Interior under slab insulation needs to connect to bottom plate. Recommend 4" CMU block with 2" rigid insulation beneath bottom plates can provide detail.	
79	WUFI Energy Model	A-402 RI	Architect	Porch slabs need insulation extending below grade and isolating porch slab from building slab.	
Wall to roof connection					
80	PHIUS detailing	A-402 RI	Architect	Connect air barrier over ZIP-R to exterior and down.	
81	PHIUS detailing	A-402 RI	Architect	Need to see detail of where flat roof meets pitched roof to detail air barrier connections.	
Certification Programs					
82	EPA IndoorPLUS			Indoor airPLUS low-emitting products documentation	While it is not necessarily the responsibility of SCI to verify compliance with all the IAP low emitting products requirements, it is necessary for the builder to provide documentation and attestation that all products are





®





NOTES

DETAILS SHOWN ARE SCHEMATIC ONLY AND ARE INTENDED TO SHOW LOCATION AND EXTENT OF AIR BARRIERS, VAPOR BARRIERS AND OTHER AIR SEALING MEASURES. REFER TO ARCHITECTURAL DRAWINGS FOR CONSTRUCTION DETAILS.

MULTI-FAMILY DWELLING UNITS ARE REQUIRED TO BE TESTED AT A PRESSURE DIFFERENCE OF 50 PASCALS WITH RESPECT TO THE OUTDOORS AND HAVE ENVELOPE AIR LEAKAGE WHICH DOES NOT EXCEED 0.30 CFM50/SQ. FOOT.

FULLY ALIGNED AIR BARRIERS

A COMPLETE AIR BARRIER SHALL BE PROVIDED THAT IS FULLY ALIGNED WITH THE INSULATION AS FOLLOWS:

- AT INTERIOR SURFACE OF CEILINGS,
- AT EXTERIOR SURFACE AND INTERIOR SURFACE OF WALLS

REDUCED THERMAL BRIDGING

ADVANCED FRAMING TECHNIQUES INCLUDE THE ITEMS BELOW:

- ALL CORNERS INSULATED 2 R-4 TO EDGE
- ALL HEADERS ABOVE WINDOWS & DOORS INSULATED 2 R-5 FOR 2X4 FRAMING
- FRAMING LIMITED AT ALL WINDOWS & DOORS TO ONE PAIR OF KING STUDS, PLUS ONE PAIR OF JACK STUDS PER WINDOW OPENING TO SUPPORT THE HEADER AND SILL
- ALL INTERIOR / EXTERIOR WALL INTERSECTIONS INSULATED TO THE SAME R-VALUE AS THE REST OF THE EXTERIOR WALL.

AIR SEALING

ALL PENETRATIONS IN THE EXTERIOR WALLS AND ROOF SHALL BE FULLY SEALED WITH SOUND BLOCKING OR FLASHING AND GAPS ARE TO BE SEALED WITH CAULK OR FOAM INCLUDING:

- DUCTS
- PLUMBING AND OTHER PIPING
- ELECTRICAL WIRING
- BATHROOM AND KITCHEN EXHAUST FANS

CRACKS IN THE BUILDING ENVELOPE SHALL BE FULLY SEALED WITH SPRAY APPLIED WATER BASED ELASTOMERIC SEALANT (EKOSEAL BY KNAUF INSULATION, ENERGY COMPLETE BY OWENS CORNING):

- AT SILL PLATES TO THE FOUNDATION,
- AT TOP OF WALL CONTINUOUS TOP PLATES
- AT ROUGH OPENING AROUND ALL DOORS AND WINDOWS

IN ADDITION:

- FOAM GASKETS ARE TO BE PLACED BENEATH WALL SILL PLATES
- DRYWALL IS TO BE SEALED TO TOP PLATE AT ATTIC / WALL INTERFACES

ALL WALL PENETRATIONS, INCLUDING MECHANICAL, FIRE SUPPRESSION, TRASH CHUTES, ETC. MUST BE SEALED TO PREVENT AIR FLOW INTO AND THROUGH THE BUILDING'S VERTICAL CHASSES.

ABOVE GRADE SILL PLATES MUST BE SEALED TO FOUNDATION OR SUBFLOOR ON ALL FLOORS

DUCTS, FLUES, SHAFTS, PLUMBING, PIPING, WIRING, EXHAUST FANS, & OTHER PENETRATIONS TO UNCONDITIONED SPACE SEALED WITH BLOCKING/FLASHING AS NEEDED.

CONTINUOUS TOP PLATES OR BLOCKING AT TOP OF WALLS ADJOINING UNCONDITIONED SPACE AND SEALED

DRYWALL SEALED TO TOP PLATE AT ALL UNCONDITIONED ATTIC/WALL INTERFACES USING CAULK, FOAM, DRYWALL ADHESIVE, OR EQUIVALENT. APPLY SEALANT DIRECTLY BETWEEN THE DRYWALL AND TOP PLATE, OR TO THE SEAM BETWEEN THE TWO FROM THE ATTIC ABOVE.

ALL DEMISING WALLS BETWEEN UNITS AIR SEALED AS EXTERIOR WALLS.

ALL PENETRATIONS INTO DEMISING WALLS SEALED.

WIRING AND ANY HOLES INTO ANY OUTLET BOX ON DEMISING WALLS AND EXTERIOR WALLS SEALED WITH CAULK OR FOAM AND OUTLET BOX CAULKED TO DRYWALL.

BLOCKING EXTENDING INTO INTERSTITIAL SPACE ABOVE DEMISING WALLS, AIR SEALED TO FORM A CONTINUOUS PLANE AND ANY PENETRATIONS SEALED.

DOORS TO HALLWAYS AND UNCONDITIONED SPACE MADE AIR TIGHT WITH WEATHER STRIPPING.

ALL WALL PENETRATIONS TO TRASH CHUTES ARE TO BE SEALED TO PREVENT AIR FLOW INTO OR THROUGH THE VERTICAL SHAFT

AIR SEALING STRATEGIES TO BE REVIEWED WITH THE HERS RATER TO MEET ALL INSPECTION REQUIREMENTS OF THE ENERGY STAR PROGRAM AND BLOWER DOOR TESTING THRESHOLDS OF EACH UNIT.

IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO PROVIDE AIR TIGHT UNITS THAT MEET THE COMPARTMENTALIZATION TESTING OF THE ENERGY STAR AND HERS RATER PROGRAMS.

Building shell air tightness requirement: 50 pa @ 0.060 CFM50/m2

1404.3.2 Code allows Class 3 vapor retarder. PHIUS recommends

Recommended to use a liquid flashing

Recommended to use a liquid applied flashing at all seams

Consider full R-value slab edge insulation. Also coordinate foundation insulation install e.g. exterior alignment with insulating sheathing

Seal bottom and top of sill sealer or similar

Consider flanged air tight electrical box



STANDARD ELECT. BOX OR OTHER DEVICE



Value in a Different Perspective



- Energy Star / Code Compliance
 - PHIUS Verification - IR Imaging



1 EXTERIOR WALL MEETS STAIR WALL
1" = 1'-0"

2 EXTERIOR WALL CORNER
1" = 1'-0"


Item	Equipment / Checklist Item	Drawing/Spec*	Responsible Party	Program Requirement	SCI Comment	Arch/MEP Response
Energy Star Rater Field Checklist						
10	Item 3.4 Wall Thermal Bridging: Advanced Framing	A5.03, S6.03	Architect	<p><i>Without the use of exterior rigid insulation, SIPs, ICFs, or Double-Wall Framing. At above-grade walls separating conditioned from unconditioned space, advanced framing (3.4.3) must be utilized, including all items below:</i></p> <p>3.4.3a: Corners insulated to $\geq R-6$ to edge</p> <p>3.4.3b: Headers above windows & doors insulated $\geq R-3$ for 2x4 framing or equivalent cavity width, and $\geq R-5$ for all other assemblies (e.g., with 2x6 framing)</p> <p>3.4.3c: Framing limited at all windows & doors to one pair of king studs, plus one pair of jack studs per window opening to support the header and sill</p> <p>3.4.3d: Interior / exterior wall intersections insulated to same R-value as rest of exterior wall,</p> <p>3.4.3e Minimum stud spacing of 16 in. o.c. for 2x4 framing in all Climate Zones and, in CZ 6-8, 24 in. o.c. for 2x6 framing.</p>	<p>Ensure all advanced framing techniques are indicated in both Architecturals and Structural Plans.</p> <p>3.4.3a: Corner needs to be framed open (California Corner) to ensure insulators can insulate the corner. Click comment for further details.</p> <p>3.4.3b: Provide additional details for insulated headers</p> <p>3.4.3c: Typical Wood Header Detail on S6.03 indicates framing may will not meet requirements at all exterior openings</p> <p>3.4.3d: Detail 9 on A5.03 does not indicate compliance with this requirement.</p> <p>3.4.3e: Requirement met</p>	




Design Considerations

- Thermal Bridging
 - Energy Star Homes & MFNCP / Code Compliance
 - PHIUS - IR Imaging

Reviewer		Isaiah Grigos / Greg Downing				
Programs		Energy Star Homes V3.1 & PHIUS+ 2018				
Plans/Specs Reviewed		2/5/2021 - 95% CD				
*Note: Where specific sheet numbers are referenced below, comments may also pertain to other sheets in the set or other buildings where similar conditions exist.						
Item	Equipment / Checklist Item	Drawing/Spec	Responsible Party	Program Requirement	SCI Comment	Arch/MEP Response
Energy Star Version 3.1 Items						
Rater Field Checklist						
4	Item 1.3: Insulation Quality	Specifications	Architect	All insulation achieves Grade I install, or Grade II is permitted for assemblies that contain a layer of continuous air impermeable insulation $\geq R-6$ in CZ 5-8. Grade II Batts are permitted to be used in floors if they fill the full width and depth of the floor cavity, even when compression occurs due to excess insulation.	Recommend adding requirement language to specifications. All exterior assemblies will need to meet Grade I installations.	
8	Item 3.2: Thermal Bridging at Slabs	S4.02 A6.02 A4.06	Architect	For slabs on grade in CZ 4-8, 100% of slab edge insulated to $\geq R-5$ at the depth specified by the 2009 IECC and aligned with the thermal boundary of the walls. (See Footnotes 15,16)	1) Indicate R value for all slab edge locations. Recommend doing this in a detail on A6.02. Insulation with R values should be indicated in both architectural and structural drawings. Cut below from A4.06 is missing the slab edge insulation detail.	




30 ELEVATOR - SECTION - AT ROOF
Scale: 1/2" = 1'-0"




11 A5.54/11 - COMPOSITE SIDING OVER CONCRETE SLAB GARAGE CURTAIN WALL
Scale: 3/4" = 1'-0"

A5.54 - Elevated slab over garage needs to be isolated and insulated. See Energy Star requirement below.



12 A5.54/12 - COMPOSITE SIDING OVER CONCRETE SLAB GARAGE
Scale: 3/4" = 1'-0"

A5.54 - Elevated slab over garage needs to be isolated and insulated. See Energy Star requirement below.




16 A5.55 - SECTION - WALL/CEILING INTERSECTION AT GARAGE HEAD
Scale: 3/4" = 1'-0"

A5.55 - Energy Star MFNC elevated slab requirements require isolating the slab and reducing thermal bridging through support columns. See full requirements below

Design Considerations



- Compartmentalization Testing
 - 0.30 CFM/SF Shell in each unit
 - NYS ECCC & PHIUS requirement
 - Important to include air sealing details at demising walls and identify who is responsible



Design Considerations



- Additional HVAC Requirements
 - ERV requirements when exhausting from kitchen
 - Room pressure testing with ERV operational.
 - Measure ERV supply and exhaust rates vs design values
 - Ability to balance system
 - ERV duct leakage
 - Watt/ CFM measurement

Item	Equipment / Checklist Item	Drawing/Spec*	Responsible Party	Program Requirement	SCI Comment	Arch/MEP Response
PHIUS MF QA Workbook						
15	Item 1.12	M1.02, M1.03	Mechanical	If kitchen exhaust connected to ERV/HRV, register is min. 6' from cooktop, MERV 3 or washable mesh filter for trapping grease, and recirc hood over range	<p>If kitchen exhaust is linked to ERV, exhaust register needs to be $\geq 6'$ from the cooktop. Majority of kitchen exhausts are indicated within this 6' restriction.</p>	

Plan Accordingly



- Optional Mid-Point Blower Door Test
 - Sequencing for this test is challenging
 - Test results are critical to catch and correct deficiencies in primary air barrier
- Final Whole Building Blower Door Test
 - Whole building testing – 0.06 CFM50/sf of buildings gross envelope area performed in both pressurization and depressurization.

	Depressurization	Pressurization	Average
Test Results at 75 Pascals:			
cfm (Airflow)	3972 (+/- 6.0 %)	9440 (+/- 3.2 %)	6706 (+/- 2.9 %)
ACH75	0.82	1.95	1.39
cfm/ft ² (Floor Area)	0.1592	0.3782	0.2687
cfm/ft ² (Surface Area)	0.1393	0.3310	0.2351
Leakage Areas:			
Canadian EqLA @ 10 Pa (in ²)	361.4 (+/- 13.2 %)	660.3 (+/- 15.9 %)	510.9 (+/- 11.3 %)
in ² /ft ² Surface Area	0.0127	0.0232	0.0179
LBL ELA @ 4 Pa (in ²)	204.9 (+/- 21.7 %)	332.1 (+/- 24.4 %)	268.5 (+/- 17.2 %)
in ² /ft ² Surface Area	0.0072	0.0116	0.0094
Building Leakage Curve:			
Flow Coefficient (C)	322.3 (+/- 34.6 %)	436.0 (+/- 37.2 %)	379.1 (+/- 25.9 %)
Exponent (n)	0.582 (+/- 0.093)	0.712 (+/- 0.093)	0.647 (+/- 0.066)
Correlation Coefficient	0.99623	0.99564	
Test Standard:	E779-10		
Test Mode:	Depressurization and Pressurization		





Image 2 - Blower Door Double Shroud Setup

Building Leakage (cfm)



Additional Program Requirements



- DOE ZERH – Hot Water Distribution Testing
- EPA Indoor airPlus
 - Radon resistant requirements
 - Low VOC products
 - Ventilation after Material Installation

Item	Equipment / Checklist Item	Drawing/Spec*	Responsible Party	Program Requirement	SCI Comment	Arch/MEP Response
EPA Indoor Air Plus						
1	Moisture Control [1.2]		Architect	Layer of aggregate or sand (4 in.) with geotextile matting installed below slabs AND radon techniques used in EPA Radon Zone 1.	Ensure project is meeting Radon resistant requirements.	
2	HVAC Systems [4.2]		Architect	Duct systems protected from construction debris AND no building cavities used as air supplies or returns	Note that duct systems need to be sealed off during construction to prevent debris from entering	
3	Item 6.1 - 6.3: Materials		Architect	6.1: All composite wood products certified low-emission. See spec. 6.2: Interior paints and finishes certified low-emission. See spec. 6.3: Carpet, carpet adhesives, and carpet cushion certified low-emission. See spec.	SCI did not see a finish schedule in plans. Ensure Low-emission criteria is met for all product selections.	
4	Item 7.2 - Final		Architect	Home ventilated before occupancy.	This requirement should be indicated in Specifications and a plan should be implemented with the property management group.	
Net Zero Energy Ready Home						
	Net Zero Energy Ready Home Checklist		Electrical	Install a 1" metal conduit for the DC wire run from the designated array location to the designated inverter location (cap and label both ends). [RERHPV Guide		
	Net Zero Energy Ready Home Checklist		Electrical	Install a 1" metal conduit from designated inverter location to electrical service panel (cap and label both ends). [RERHPV Guide		
	Net Zero Energy Ready Home Checklist		Electrical	Install and label a 4' x 4' plywood panel area for mounting an inverter and balance of system components. [RERHPV Guide 3.1] Alternative: Blocking is permitted to be used as an alternative to the 4' x 4' panel. The area designated for the future panel to mount PV components shall be clearly noted in the system documentation		
	Net Zero Energy Ready Home Checklist		Electrical	Install a 70-amp dual pole circuit breaker in the electrical service panel for use by the PV system (label the service panel) [RERHPV Guide 3.4] Alternative: Provide a labeled slot for a double-pole breaker in the electrical		



Indoor airPLUS Version 1 (Rev. 04) Verification Checklist




Home Address:		City:	State:	Zip:	
Climate Zone (1-6):		Radon Zone (1-3):			
Section	Requirements (Refer to full Indoor airPLUS Construction Specifications for details)	Must Correct	Builder Verified	Rater Verified	N/A
ENERGY STAR v3	Note: The Rev. 04 checklist reflects only the additional Indoor airPLUS requirements and their corresponding section numbers that must be met after completing the ENERGY STAR requirements. ENERGY STAR remains a prerequisite for Indoor airPLUS qualification.	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
	ENERGY STAR Version 3 (or 3.1, 3.2) Program Requirements must be followed and the home shall be ENERGY STAR certified in conjunction with Indoor airPLUS qualification.	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Moisture Control	1.1 Drain or sump pump installed in basements and crawlspaces. In EPA Radon Zone 1, check valve also installed. Exception Applied: <input type="checkbox"/> Slab-on-grade foundation <input type="checkbox"/> Free-draining soils	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	1.2 Layer of aggregate or sand (4 in.) with geotextile matting installed below slabs AND radon techniques used in EPA Radon Zone 1. Exception Applied: <input type="checkbox"/> Slab-on-grade foundation <input type="checkbox"/> Free-draining soils <input type="checkbox"/> Dry climate	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	1.4 Basements/crawlspaces insulated, sealed and conditioned. Exception Applied: <input type="checkbox"/> 100-year flood zone <input type="checkbox"/> Marine climate <input type="checkbox"/> Dry climate <input type="checkbox"/> Crawlspace sealed with capillary break and active dehumidification <input type="checkbox"/> Raised pier foundation with no walls	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	1.7 Protection from water splash damage if no gutters. Exception Applied: <input type="checkbox"/> Rainwater harvesting system <input type="checkbox"/> Dry climates	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	1.11 Supply piping in exterior walls insulated with pipe wrap. Exception Applied: <input type="checkbox"/> Dry climate AND climate zone 1-3 <input type="checkbox"/> Air barrier insulation in wall cavity	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	1.14 Hard-surface flooring in kitchens, baths, entry, laundry, and utility rooms.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Radon	2.1 Radon-resistant features installed in Radon Zone 1 homes in accordance with Construction Specification 2.1. Exception Applied: <input type="checkbox"/> Perimeter pipe loop in lieu of full aggregate (dry climate) <input type="checkbox"/> Manufactured home with raised pier foundation	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Pests	3.2 Corrosion-proof rodent/bird screens installed at all openings that cannot be fully sealed. (Not required for clothes dryer vents.)	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
HVAC Systems	4.1 Equipment selected to keep relative humidity < 60% in "Warm-Humid" climates. Exception Applied: <input type="checkbox"/> Climate zones 4-8, 3B, 3C and portions of 3A and 2B	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	4.2 Duct systems protected from construction debris AND no building cavities used as air supplies or returns.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	4.3 No air-handling equipment or ductwork installed in garage.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	4.6 Clothes dryers vented to the outdoors or plumbed to a drain according to manufacturer's instructions.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Combustion Pollutants	4.7 Central forced-air HVAC system(s) have minimum MERV 8 filter AND no ozone generators in home. Temporary filter installed to protect unit from construction dust.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	Emissions standards met for fuel-burning and space-heating appliances.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	5.1 Identify appliance type: <input type="checkbox"/> Masonry heater <input type="checkbox"/> Factory-built wood-burning fireplace <input type="checkbox"/> Wood stove <input type="checkbox"/> Pellet stove <input type="checkbox"/> Natural gas/propane fireplace Appliance model name/number: _____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	5.2 CO alarms installed in each sleeping zone (e.g., common hallway) according to NFPA 720.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	5.3 Multifamily buildings: Smoking restrictions implemented AND ETS transfer pathways minimized.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
5.4	Attached garages: Door closer installed on all connecting doors.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	Attached garages: In homes with exhaust-only whole-house ventilation EITHER <input type="checkbox"/> 70 cfm exhaust fan installed in garage OR <input type="checkbox"/> Pressure test conducted to verify the effectiveness of the garage-to-house air barrier.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>




Building Durability

- In addition to Program Checklist review, another set of eyes may help catch issues that potentially compromise building durability



A5.57 – If inverted attic assembly, spray foam should link the two exterior walls together via underside of roof deck



A5.53 – Spray foam should link with the rigid insulation above the roof deck



The Field Issues Persist..

- Involvement in design improves awareness to compliance items in the field and builds rapport with construction personnel
- Early on-site meetings with the GC and trades will allow for discussion of the inspection requirements and troubleshoot potential issues from their perspective



PHIUS+ Certification Process



Schematic Design: Initial Layout and Systems



Pre-Certification: Approved Modeling and CD's



Construction Inspections: Insulation & Air Sealing Checks



Final Testing: Air Tightness & Commissioning



Certification: Final Certifications

High-Performance
Home Staircase





Case Study – CreekView Apartments Phase I

Features

- 96 Units in 12 Buildings
- 8-Plex Design, mix of 1, 2, and 3 bedroom units
- Programs:
 - PHIUS+ 2015
 - NYSERDA Low Rise
 - Energy Star Homes V3.1
 - DOE Net Zero Energy Ready
 - EPA Indoor AirPlus





Insulation Levels

Wall Insulation

- R-37 Wall
 - 2x6 Wood Studs - R-21 Batt
 - OSB Sheathing
 - Fluid Applied Air Barrier
 - 3.5" Exterior Panel R-19 (Polyiso + Osb)
 - Tyvek weather barrier
 - Vinyl Siding





Insulation Levels

No Thermal Bridging

- Continuous insulation at walls
- Porch point connections
- Storage room held away
- Foundation walls held away





Insulation Levels

Windows/Doors

- Triple pane insulated
- Casements/Fixed for air tightness
- ADA sills vs. air tightness
- Fall protection?







Insulation Levels

Sub-Slab Insulation

- R-15 Underslab Insulation
 - 3" EPS Foam
 - Vapor Retarder
 - Concrete Slab
- Slab Edge Detailing
 - 2" vertical slab edge
 - 4" exterior foundation wall



Foundation Insulation Inspection





Attic Air Sealing

Ceiling Insulation

- R-60 to R-80 Wall
- OSB Sheathing as primary air barrier
- Taped seams
- Drywalled ceiling






Mechanical Systems

Ventilation

- Panasonic FV-10VEC1
- Continuous Exhaust
 - Bathroom: 20 CFM
 - Kitchen: 25 CFM
- Supply register to each room
- Range hood recirculating





Mechanical Systems Installation

Install air source heat pumps off the ground adequate for snow not to interfere with operation




The Value of Verification

Identifying major constructability items that may have been overlooked

Preparing for and performing the whole building air tightness testing/Compartmentalization

Important to catch design/product issues early, ideally at air sealing or open wall inspection

PHIUS verification overlaps with other energy green program requirements





Foundation Insulation Inspection





Install Coordination





Primary Air Barrier Failure





Fluid Applied Air Barrier

Concept



Reality



Result





Preliminary Testing

Interior Spray Foam

Test 1: Initial Pre-Test
970 CFM50

Test 2: Spray Foam Interior
862 CFM50

Target: Continuous Air Barrier
706 CFM50





Continuous Ceiling Air Barrier

Concept



Reality



Result





Quality of Install





Connections





Building Components





Material Selection





Reality





Material Compatibility





Air Sealing Detail Verification





Air Tightness Testing

Air Tightness

- Continuous air barrier across building
- Air tight windows (casement) and doors
- Buildings meet 0.05 CFM₅₀/sf of Shell
- Testing occurred pre-drywall and final






Air Tightness Testing

Results:

- Target: 0.05 CFM₅₀/sf of Shell

UNIT	ENVELOPE AREA	TARGET
		BLOWER DOOR TARGET (@50Pa)
3 Bedroom	17,192	860
2 Bedroom	14,113	706
1 Bedroom	11,481	574



Label	Base?	start	end	nobs	Nominal Avg Pressure	Nominal Total Flow
	True	20	137	118	-1.31	0
	False	1414	1432	19	-60.9	811.7
	False	1507	1526	20	-52.09	713
	False	1595	1611	17	-49.98	696.3
	False	1620	1639	20	-43.81	631.4
	False	1718	1736	19	-35.88	556.5
	False	1818	1837	20	-26.04	439.4
	False	1926	1945	20	-11.71	213.9
	True	2507	2623	117	-97	0

Reporting Pressure (Pa)

Test to View

Average of Press and Depress

Airflow at 50 Pascals
 690 cfm +/- 1.6 %
 Range: 670 to 701
0.049 CFM @50/sq ft (0.023 to 0.024)

Leakage Areas
 EqLA (10 Pa) = 55.9 in² +/- 3.5 %
 ELA (4 Pa) = 26.0 in² +/- 6.0 %

Building Leakage Curve
 Coef. (C) = 30.3 cfm/Paⁿ +/- 10.0 %
 Exponent (n) = .800 +/- 0.024
 Correlation Coef. (r) = .99898
 Corr Coef Squared (r²) = .99795

[View / Edit Test Details](#)

[Export to Tectite Express...](#)

[USACE Report](#)

[OK](#)

Copy Data Table to Clipboard



Air Tightness Testing





Final Verification

Additional Verification

- Hot Water Distribution
- Ventilation Flow Rates
- Ventilation wattages
- Final equipment efficiencies





Certification

Timeline:

- PHIUS+ Verifier submission for review
- Completed PHIUS+ Workbook
- Verification Picture
- Thermal Imaging
- Finalized additional certifications
 - NYSERDA Low Rise New Construction
 - Energy Star Homes V3.1
 - DOE Net Zero Energy Ready
 - EPA Indoor AirPlus





CreekView Apartments Ph 1



a DiMarco Group company

DIMARCO
GROUP



Glasow Architecture



Special Thanks to the Project Team!



CreekView Apartments Phase II

How to get a PHIUS Project to Net Zero?

- Size of roof now dictates source energy, how to reduce building loads to fit in budget of roof produced solar.
- Geothermal heating/cooling/DHW central per building
- Central ERV systems to reduce construction and maintenance cost
- Solar PV – Owner paid remote net metering
 - Owner pays all utilities for the project
 - 108 Individual Electric Meters – 1 apt meter + 1 blg meter
 - Solar PV on each building tied into 1 owner meter

CreekView Apartments
Canandaigua, NY


Early Design
\$1 Million Award



Integrated Process



- Feedback from all contractors for ideas welcomed
- Regular check points to reassess project goals
- Net-Zero goal dictates final loads of the building
- Solar capacity constrained by roof sizing and orientation
- Building orientations optimized
- Insulation and equipment sized to solar capacity



Questions?

Greg Downing
greg@greenrater.com

Chris Straile
chris@greenrater.com

