Multifamily Construction Verification – Planning for Success

Mike O'Donnell

2018 PHIUS North American Passive House Conference

Steven Winter Associates, Inc. 2018


Overview of Presentation

- PH Basics
- Construction Phase QA/QC
- Case Study Beach Green North
- Planning Final Blower Door Testing
- Recommendations for Success

PH BASICS

Multifamily

ELEMENTS OF A LARGE MULTIFAMILY PASSIVE HOUSE BUILDING



MULTIFAMILY CONSIDERATIONS

Energy Recovery Ventilation Determining the right system for any project can be challenging. There are pros and cons to both central and decentralized systems. A certified Passive House consultant can help the project team decide which system is best for your building.

Domestic Hot Water


In large scale multifamily buildings in the US the majority of DHW systems are central systems with recirculation loops and high efficiency, natural gas water heaters. Minimizing pipe lengths and optimizing pump sizes and insulation are essential to meet the rigid Passive House primary energy and cooling thresholds.

Efficient LIghts & Appliances Multifamily projects face special challenges here because they must run corridor and egress lighting 24/7. They are also faced with a greater number of appliances per square foot compared with single family homes. Both of these factors result in increased cooling and primary energy demands. The use of controls and daylighting should be incorporated wherever possible to reduce energy use.

PHI vs PHIUS: Differences

Requirement	PHI	PHIUS	Notes
Comfort criteria	Mandatory	Recommended	Leads to triple pane windows in NYC for PHI
Whole building energy demand	/ft² of conditioned envelope	/person	
Heating demand	Same for all climates	Changes based on climate	
Cooling demand	Changes based on latent load from climate and occupant density & internal loads	Changes based on climate, sensible only	Temporary adjustment being allowed for cooling demand by PHIUS
Air Tightness	0.6 ACH50 required / 0.033 cfm/ft2 of façade recommended for large buildings	0.08 cfm/ft2 of façade for 5+ stories & non- combustible, 0.05 cfm/ft2 for all others	
Ventilation	Not a lot of approved ERVs in US	Approve a lot more ERVs	
Cooling & Heating Loads	Can certify based on demand or load	Must meet both demand and load thresholds	Can be difficult to meet both

Blower Door Testing



Blower Door Testing – Whole Building



CONSTRUCTION PHASE QA/QC

PH Contractor Buy-In

- General contractor and subcontractor buy-in is critical to project success
- All trades have an impact on project results and may require a mind shift on performance testing
- Passive House Tradesperson training mandatory for key personnel
- GC needs at least two people who will be dedicated to PH scope and coordination

PH Contractor Buy-In

• Ensure GC & trades fully understand what's included in respective work scopes

10

- Ask questions, dispel myths
- Discuss expectations with whole project team during bidding phase





Verification for Large Projects


- Foundations
 - Abutting neighbor(s)
 - Staging of foundation
 - Under slab / stem walls
- Above Grade Walls
 - Wall construction type: CMU, wood framed, etc.
 - Sequencing for hoistways, upper vs. lower floors
- Roof
 - Thermal breaks and roof membrane penetrations
 - Bulkheads, louvers & dampers





Verification for Large Projects

- MEP
 - In unit heat/cool duct testing
 - Ventilation
 - TAB process
 - Pipe insulation
 - Lighting wattages & controls



Typical & Unique Checklists

	Sloven Writer Associates, Inc. September 24 8-08 Orderwood Base 1172					
	Beach Green Dunes Phase II 4518 Rookaway Beach Bhd, Far Rookaway, W11981 Inspectors for 2015 External Aven Control (2005) and Patient Insun (PHUDF) - Typical List					
	NOTE: Items in red are specific to Passive House and are highlighted to call attention to these requirements. SWA to inspect the final installation of each item to verify compliance and then periodically thereafter to ensure consistency of en					
	Construction Inspection Item Timeline			Details		
		Sub-slab vapor barrier Underslab and	in progress, prior to concrete pouring	 Sub-slab vapor barrier verification for EGC. Contractor photos are acceptable. 		
		Undersiab and below grade well insulation	in progress, prior to becifii	 Insulation at pile caps and elevator pit installed at correct thickness with boards tightly joined together with no pape. 		
Start of	but of Construction	Above grade air barrier	At commencement, every 1-2 foors	• Welf-Mindow modag review and best - Addies 2 15 bestävel oper manufacturer at blick ansas. Transitions at slab odges. Window opening Starbing. - Die dold Cale Interdiad oper manufacturer at STPI ansas ill window opening Starbing datab. - Bio dold Cale Interdiad oper manufacturer at adjustet biologing exess. Segaencing and bodd up reveal to adow Prospere offrage and interarer histores at the addieses.		
Construction	Start of O	Above grade Insulation	At commencement, every 1-2 foors	• All inclusion service to italiation concertainsess the strategies, built ass, and any other methods percentaining the localized in type - concertainsess the strategies, built ass, and any other methods are strategies. The strategies are the party and particular the strategies are strategies and and any other strategies are strategies. The strategies are strategies and the strategies are strategies and any other strategies are strategies and any other strategies are strategies and the strategies are strategies and any other strategies are described and any other than the strategies are an adjust to the garage in terms of bioleses and continuous. Heating and advances are strategies and any other strategies are and biologies and any other and any other strategies and strategies and any other strategies are and biologies and continuous.		
		Interior framing	At commencement,	Run drywall to the exterior wall at partitions between dwelling units and seal the joint at that intersection		
		layout for air sealing	every 1-2 foom At commencement	(overlaps with Restopping) for compartmentalization. - Sincks testing of penetrations and envelope transitions to be conducted throughout construction. Including:		
		Building envelope air sealing	concentrated early in the construction	 ances stating of persentations and serverage stantations to be conducted throughout construction. Industry: - Walkindow traditis - Hommatise apotheting (sampling of windows, doors, & ungule norms e.g. gas meter morn) - Hommatise apotheting blower door (final lists, are being) - Hold (sampling) - Hommatise apotheting - Hommatise - Hommati		
			process			
Prior to Drywall /	nd definition	Duct sealing	Prior to enclosure with drywell shafts	Dacheed through sealed with marks for all HAAC splanes. Do not pit during the dealing. Advice politics of the adding and the political politics. Provide a module of the political politics. Provide a model and political political political political politics. Provide a model and political political political politics. Provide a model and political political politics. Provide a model political political political politics. Provide a model political political politics. Provide a model political political politics. Provide a model political political political political politics. Provide a model political political political political politics. Provide a model political political political political political political politics. Provide a model political politi		
Start of Drywall		Roof insulation	When work is in progress	Proper thickness and all insulation boards are tightly adjoined with no gaps.		
	190		progress	 SWA must inspect the installation in progress. Ensuring proper insulation thicknesses for domestic hot water (including conture), domestic cold water, heating hot water, ground acure water, and invitignment lines. Exterior piping insulation to be protected in accordance 		
Installation	hiorto Drywal / Start of Drywall Installed on	Pipe insulation Duct insulation	At commencement, in progress, prior to drywail enclosure	har weite, no ground source weiter, and integrent lines. Editor ploya insulation to be protected in accordance with energy code. • Observe proper Frankles and bridness of duct insulation. • Observe proper insulation and alreading of duct insulation and vapor barrier on ducto between ERVe & the warrier.		
	8	Window & door Installation and sealing	At commencement, every 1-2 floom	Testing as described above in the building envelope air sealing section Visual trapections for remaining window instaliations		
	Æ	Drywell installation, air sealing visual inspection	When work is in progress	- Ensuring drywall seams are sealed to the celling, foor, and each other - Air sealing details to be observed being implemented as catilised in the develops - takail center that or initialing (ARM #05073 company) beind takibinesr exclasures		
		INAC equipment Installations	Once on site, after all equipment installations	· HuRC equipment to match schedules, meet efficiency requirements, and have associated controls installed		
		Water heater room drain	When work is in progress	Provide floor drain in water heater room (DGC)		
		Roof drains	Prior to enclosure with dryweil shafts	Fool drain lines installed and insulated		
		Lighting and lighting controls	At commencement, at 100% completion	 Upting and lighting controls (e.g. occupany sensors) where required. Keep boxes of LED fotures to confirm makes/models. 		
		Applances, occupant waste &	Once arrived at the site	ENERGY STAR appliances and leased clothes washers, model numbers for dryers Provide electric storwhangelovens		
		Roof membrane & roof pevers	Upon Installation	Provide set-sets atoversage/owers Provide 1 wask - 2 moycling bits per unit and in community mome + seale DISEGY 67A6 coeffed months per unit and in coefficient + value DISEGY 67A6 coeffed months pairs atomic metals are refectance of 0.3. (DSC) - Vehancement coefficient Digits coeffed with minimum sate reflectance of 0.3. (DSC)		
				 All installed plumbing futures (tollets, kitchen faucets, bethroom faucets, shower heads) are the correct GPM flow rates as required by EGC and Water Genes labeled as needed. 		
		Plumbing futures & water metering	Sampling of apartment units	-Weter meters installed on each tollet and isundry facilities, the boiler makeup veter, outdoor water, and water consumption in my commercial spaces. Conduct pressure-loss tests and visual impections to determine if there are any tests. This may least faculd, (EOC)		
		Air tightness testing	Sampling of apartment	are any team. To any weak touch (EOC) • Apartments must pass leakage teating maximum of 0.30 CFMBSD per square foot of enclosure = 04WA recommends teating a sample modulo unit as early as possible		
		(blower door) Exterior door sealing	At 100% completion	- SWA recommends testing a sample mockup unit as early as possible - All exterior doors are assied with weathentipping & door sweeps		
		Air tighthese testing	Whole building blower door test. At 100%	* All asserter docts are assest wen weatherstopping is door several = Building must pass leakage teeting machinum of 0.00 CPMSD per square four of enclosure = Building systems must be put to operating state as utilities in the Blower Door Test pilon		
Construction	5	(blower door)	completion			
Completion	Condituction Completion	PHUS+ Verflation	At 100% completion	Process difference interes the karp op solitie spec and approximation is the time. The same grift is in Provident of the second of the second on the second of the second of the second Provident of the second of		
		CRV texting	Sampling of apartment units, no less than 10 units ready at one time	ERV supply 5 whows from a the least 100% of design flow and within 10% of each other. If Row as each negliser must be within 20% of 5 and 5 design flow, whichever is greater. Heasaward is parallel difference or was been the flectioner and Molg space when the CRV system is openating and the doors are closed Access to mait huncio combing of the CRV is required for this setting (PNUD to confirm).		
		GGHP testing	Sampling of apartment units, no less than 10 units ready at one time	 Total gatem flow must be within 15% of sealing. Now - InterColl flow at each ingiter must be within 25% or 25 cm of design flow, whichever is greater. - Measured 3 pascal difference or lease between the backnown and bring space when the GGHP and ERV aptimum are operating and the doors are duated 		
		Metering (electric) Landscaping	At 100% completion At 100% completion	Tenants are individually metered for electricity (meter banks) Ensure landscaping and intgation meet DGC requirements		
	*Construction	n Waste Manageme	nt reports to be subm	alled to SWA throughout the project, as they are received from the waste hauler.		
				ever.		



Steven Winter Associates, Inc.

Beach Green Dunes Phase II

Site Inspection Checklist - Unique Conditions

General Contractor:	L+M Builders Group	Project Lead:	Thomas Moore
Primary Contact:	Andrew Canarte / TBD	Primary Inspector:	Mike O'Donnell
Date:	4/17/2018	Project Manager:	Lois B. Arena
Rev:	0	Project Number:	BGNII1A

The following items must be inspected and/or tested by SWA before being made inaccessible.

Project Phase	Item #	Description	
	U-1	Elevator Pit Insulation	
Below Grade	U-2	Below Grade Insulation	
Below Grade	U-3	Floor Insulation in Lobby Areas	
	U-4	Connection from Below to Above Grade	
	U-5	Compactor Room	
	U-6	Gas Meter Room	
	U-7	Water Room	
	U-8	Laundry Room	
	U-9	Electrical Room	
	U-10	Refuse Rooms (Floors 2 - 8)	
	U-11	Seismic Gap Corners	
Above Grade	U-12	Flood Vents	
Above Grade	U-13	Detention Tank	
	U-14	Air Sealing at Garage Beam	
	U-15	Air Sealing at Garage Ceiling to Wall Connection	
	U-16	EIFS Expansion Joint	
	U-17	Shelf Angle Attachments	
	U-18	Storefront Air Sealing	
	U-19	Canopy Connection & Drain Insulation	
	U-20	Connection from Wall to Roof	
	U-21	Mechanical Equipment Supports	
	U-22	ERV Mechanical Curb	
	U-23	PV Supports	
Ten Out	U-24	Roof Drain Insulation	
Top Out	U-25	ERV Roof Penetration	
	U-26	Typical Plumbing Penetration - Roof	
	U-27	Exhaust Ventilation Penetration	
	U-28	Smoke Dampers	

Please note that this guide is not meant to replace the drawings or specifications laid out by the architect or provide a fully exhaustive list of areas where these issues may occur.

13

Testing Tools and Protocols

- Window mockup testing
- Interim guarded blower door testing
- Interim whole building test if schedule and sequencing allows
- Envelope compartmentalization and window testing
- Unique component testing
- Whole building blower door test

Mock up








CASE STUDY

BEACH GREEN NORTH Affordable Housing – 101 units


QUEENS, NY

Wall Inspections




• ICF doesn't require as many inspections for insulation and air barrier

1st Window Mockup



2nd Window Mockup





Site Visit Reports

ltem #	Description	Image
	2 nd Floor Slab Edge Insulation: Refer to architectural details 20 A-356.	
	Detail 20 shows 4" thick insulation at the slab edge between the CUP and the Residential Tower extending 2" above and below the slab (highlighted area in detail at right)	Verhalter and and a set an
	detail at right).	
	This conditions exits at the area highlighted on the plan to the right.	

Issues Log

	3				Issues	Log - 1/2	25/2017					
SVR #	SVR Iterr ‡	lssue Type	Location	Issue	Found by 🖵	Date Foun-	Action Required	Responsible Party 💡	Reinspection Required? ₊	Actions Taken/Updates	Date Verified/ updater *	Open/ Closed
7	1	ENV	7th Floor	Panel Insulation at Joints: Insulation at the panel joints was found to be around 6 inches deep. Shop drawings indicate 9". (EEWS Shop Drawings Sheet 501, Detail 1, second image right). SWA notified Monadnock of the issue. Monadnock followed up with a photo on 5/11/16 and informed SWA that EEWS will continue to install insulation at 9 inch depth. All panels below the six floor will need to be inspected for insufficient insulation and corrected if needed via exterior scaffolding when exterior caulk is applied.	SWA	5/10/16	Photo documentation using a measuring device will be required to verify PH compliance. SWA & EEWS to agree on frequency of photos and method of depth venfication.	Eastern	Ŷ	On 9/22/16, Eastern issued photos of joint insulation being installed along two swing stage areas (Rig 3 Drop 2 and Rig 3 Drop 4). SVVA will continue keeping track of Eastern's progress.		Ongoinç
24	2	ENV	2nd Floor	Gap at the corner of storage room and condenser porch located behind the column is not air sealed at this time. Neither is the connection of Intesana to block. SWA to inspect when complete.	SWA	B/9/16	Monadnock to send photos of the area to SWA	Monadnock	N			Open
42	з	HVAC	All Floors	Damaged Ductwork Covers: SWA observed numerous instances of damaged ductwork opening covers damaged or loose throughout the first and second floors. SWA believes a significant amount of dust has likely accumulated in the ductwork. The project is now at risk of losing a LEED point needed for LEED Platinum certification.	SWA	11/21/16	Monadnock to make sure that all ductwork openings have been covered on floors 1, 2, 15-25. Monadnock to issue written confirmation to SWA once this work has been complete. SWA to spot check these areas in its next visit.	SWA	Y	On 11/3D/16, SWA observed that much of previously noted loose and damaged ductwork opening covers were repaired. Issues still persist on the various floors. SWA performed spot checks on floors 1, 2, 15-25 and found issues in all floors. On 12/1/16, Monadnock emailed SWA notifying that floors 1, 2, and 15-25 had been reinspected and damaged ductwork covers had been repaired. On 12/12/16, SWA observed issues on floors 1, 2, and 17.		Open
n/a	n/a	ENV	2nd Floor	Insulation under 2nd floor condensor porch ballast was covered before SWA could inspect. Images showing insulation depth and coverage must be provided.	SWA	5/24/16	Monadnock possesses photo documentation that shows depth and coverage. Provide images to SWA.	Monadnock	ы	On 7/28/2016, Monadnock sent photos showing depth of insulation at condensor porch ballast.	7/28/2016	Closed
n/a	n/a	ENV	26th & 27th Floor	Roof deck insulation inside AHU curb was covered before SWA could inspect. Images showing insulation depth and coverage must be provided.	SWA	5/1/16	Monadnock possesses photo documentation that shows depth- and coverage. Provide images to	Monadnock		On 10/1/2016, SWA received photos from Monadnock showing blurry tape measurements of insulation at the AHU curbs. On 10/24/2016, SWA	10/24/2016	Closed

Sample from Cornell Tech

Progress

- AeroBarrier by Aeroseal was utilized
- 6/24/2017 envelope leakage test performed but couldn't finish, Building Department shut down site for working on Saturday
- 7/6/2017 infiltration test for energy model passed!!
- ERV testing & commissioning completed
- <u>4/4/2018 PHIUS Certification received!!!</u>

PLANNING FINAL BLOWER DOOR TESTING

Blower Door Test Conditions



Steven Winter Associates, Inc. Improving the Built Environment Since 1972

WHOLE BUILDING INFILTRATION TESTING PLAN

TO DETERMINE COMPLIANCE WITH PHIUS+ AIRTIGHTNESS REQUIREMENTS AT SAINT JOHN NEUMANN

MAY 8, 2017 UPDATED JUNE 22, 2017



Key: HVAC Contractor; Plumber; GC / Builder

Intentional Opening	Test Setting	Notes
Windows, doors, skylights in the building enclosure	Closed and latched	
Doors and operable windows inside the test enclosure	Open	Use stairways to connect all zones of the building
Fire dampers	Remain as found	
Dryer doors	Closed and latched	
Gas meter room	Door to gas meter room closed and weather stripped	
Waste handling system	Trash chute termination at roof taped off. Door to trash rooms closed.	
ERVs (apartments)	Fan off, any dampers closed. Ducts to the outside sealed inside the ERV cabinet in each apartment.	Ventilation is continuous, so can remain taped off
Motorized dampers: ERV-4 (cellar)	Fan off, dampers closed. Taped off from the exterior	Ventilation is continuous, so dampers closed and sealed off
Motorized dampers: ERV-5 (1 st floor)	Fan off, dampers closed. Taped off from the exterior	Ventilation is continuous, so dampers closed and sealed off
Motorized dampers: ERV-2A (1 st floor)	Fan off, dampers closed. Taped off from the exterior	Ventilation is continuous, so dampers closed and sealed off
Motorized damper: Laundry Room (2 nd floor)	Fan off, dampers closed. Taped off from the exterior	Untaped for Method A test
Motorized damper: ERV-2 (2 nd floor)	Fan off, dampers closed. Taped off from the exterior	Ventilation is continuous, so dampers closed and sealed
Motorized dampers: EMR (1* floor), Stair A, Star B, Elevator, Boiler Room (roof)	Taped off from the exterior	Untaped for Method A test
EDV 2 (reaf)	Ean off domnors alaged	Vestilation is continuous, es

Whole Building Test Logistics

- Enough fans, cruise manometers, frames, shrouds, tubing, CAT5 cabling, people?
- Is building access limited to avoid people opening and closing doors, windows, etc.?
- Thorough walkthrough the day prior to test date to confirm prep has taken place?
- GC and appropriate subs on site to help with building prep and issues that come up on the test day?
- Saturday work permits pulled?

Central ERVs & Blower Door

- Need to seal off ERVs for the final test
- Wrap rooftop ERVs or seal exterior intake and exhaust louver ports



Individual ERVs & Blower Door

• Typically can't reach all vents to seal from outside



 Tape off both outdoor connection ports inside every ERV



• Some ERV's can't be sealed inside the cabinets

Whole Building Test Logistics

 A great resource is Blower Door Applications Guide: Beyond Single Family Residential PDF (Brennan, Clarkin, Nelson, Olson, Morin)





Blower Door Applications Guide: Beyond Single Family Residential

By Terry Brennan and Mike Clarkin of Camroden Associates And Gary Nelson, Collin Olson and Paul Morin of The Energy Conservatory

RECOMMENDATIONS FOR SUCCESS

Do This 🗸

- Insist on
 - Training for construction staff
 - Mockups
 - Interim blower door testing
- Advanced Planning
 - Typical and unique checklists
 - Blower door testing plan
- Quality Control
 - Typical details readily available on site for all subs
 - Communication between GC and PH verifier
 - Panelized construction, if applicable

Do NOT Do This ×

- Be wary
 - Assume if the GC has done a PH project that the second will automatically pass
 - Keep going without passing the window mockup
 - Depend on subs understanding contract docs without communication
 - Allow the GC to exclude meeting PH requirements from the contract
- Ignore your PH Consultant!!!!!



Questions? modonnell@swinter.com

THANK YOU!

Steven Winter Associates, Inc. NEW YORK, NY | WASHINGTON, DC | NORWALK, CT